

# Featured BBD Past Job Performances

<b>Project Title</b>	Hagers Slough Levee Improvement Reclamation	Contract Amt.	\$1,430,000
<b>Location</b>	Beardstown, IL		
<b>Description</b>			
<p>This project included the construction of a seepage berm by dredging approximately 100,000 cy of sand out of the Sangamon River and using it to construct the seepage berm sand dredged out of the same river to construct a wetland mitigation berm inside the banks of the river designed for breeding turtles.</p> <p>In addition, another 34 acres of wetland mitigation to be completed by planting a mixture of wetland trees. The trees were a mixture of saplings, and bushes in 3, 5, and 15-gallon pots.</p> <p>Our onsite management with the Land Owner/Sponsor of this project consisted of continuous communication and reporting to arrange ingress/egress, weather conditions, and the set-up of new disposal sites for a clean and efficient work site. This relationship resulted in the sponsor hiring BBD for additional private wetland mitigation.</p>			
<b>Role Performed</b>	<b>Contract Status</b>	<b>Performance</b>	<b>Completion Date</b>
Prime Contractor	Complete	100% Self-Performed	12/21/2017

<b>Project Title</b>	L-246 Levee Rehab – W912DQ-18-C-0002	Contract Amt.	\$430,000
<b>Location</b>	Charlton River – Central Missouri		
<b>Description</b>			
<p>Multiple Levee Slide Repair &amp; Riprap Placement of approximately 11000 tons of riprap on the side slope of the Chariton River.</p> <p><b>To Date:</b> 50% of the rock for this project has been laid. The rock is being stockpiled with end dump trailers in the staging area, reloaded into haul trucks and taken to be placed on the side of the levee bank. This material that is being placed has a gradation of 100% less than 700lbs, 30-40% less than 100lbs, and 0-15% less than 5lbs.</p>			
<b>Role Performed</b>	<b>Contract Status</b>	<b>Performance</b>	<b>Completion Date</b>
Prime Contractor	In Process	100% Self-Performance	Estimated Completion: Fall 2018

<b>Project Title</b>	Trost-Broshard Wetland Construction	<b>Contract Amt.</b>	\$350,000
<b>Location</b>	Concordia, KS		
<b>Description</b>			
<p>The project included construction of 5.3 miles of wetland berm of approximately 85,000 cy. The berm material was loaded by a track hoe and trucked out of the borrow area. The material was then dumped in the designated location. A grade control dozer finished and shaped the berms to the nearest .2 ft. While construction berms 4 water control structures installed by BBD were used drain the wetland. Compaction equipment was used to ensure the compaction was to specifications and structures were installed to the nearest .1 ft. After completion of the berms wetland restoration was achieved using native vegetation of approximately 100 acres</p> <p>Construction and contract management led to additional opportunities to bid on private work for the Kansas Parks and Recreation.</p>			
<b>Role Performed</b>	<b>Contract Status</b>	<b>Performance</b>	<b>Completion Date</b>
Prime Contractor	Complete	95% Performed	08/2017

<b>Project Title</b>	North Central Missouri Water Commission Clean-Up	<b>Contract Amt.</b>	\$172,000
<b>Location</b>	Milan, MO		
<b>Description</b>			
<p>Project consisted of building a new 2700-acre water supply lake for 13 counties in North Central Missouri. This project was an IDIQ contract which BBD was one of the participating contractors for the new lake basin.</p> <p>The project included demolition of structures, clean-up of old dump sites, decommissioning of wells, and seeding.</p> <p>The 3000-acre site location had multiple landowners, ingress/egress, property lines and work location which needed special handling since many of these long-term land owners had lake front land and were required to sell their property. Proper communication and diplomacy was critical in the handling of disgruntled land owners.</p>			
<b>Role Performed</b>	<b>Contract Status</b>	<b>Performance</b>	<b>Completion Date</b>
Prime Contractor	In Process – As Needed	100% Self-Performance	TBD

<b>Project Title</b>	Subdivision Onsite Bio Retention Ponds	<b>Contract Amt.</b>	\$86,000
<b>Location</b>	Leawood, KS		
<b>Description</b>			
<p>Project involved creating onsite storm water run-off storage for a newly developed subdivision. Project included grading, excavation, hauling, mixing special soil into the site, planting wetland seed mixes, along with fertilizing and mulching.</p>			
<b>Role Performed</b>	<b>Contract Status</b>	<b>Performance</b>	<b>Completion Date</b>
Prime Contractor	Complete	100% Self-Performed	12/2017

<b>Project Title</b>	Taylor Sterling Town Home Development	Contract Amt.	\$350,000
<b>Location</b>	Leawood, KS		
<b>Description</b>			
The project was a complete design/build of a new townhome development where BBD designed all landscaping, retaining walls, irrigation systems, site-drainage and monuments. The installation included 23,000 sq. yds. of blue-grass sod, 1200 tons of river rock in beds, 317 trees, 1760 plants, and poured all concrete for monument bases, sidewalks and walking trails.			
<b>Role Performed</b>	<b>Contract Status</b>	<b>Performance</b>	<b>Completion Date</b>
Prime Contractor	Complete	100% Self-Performed	2017

<b>Project Title</b>	Crescent Creek Revitalization	Contract Amt.	\$310,330
<b>Location</b>	Raytown, MO		
<b>Description</b>			
Project involved the construction of multiple single-family housing units which included earthwork, concrete slabs, sidewalks, basements, framing, windows, insulation, siding, painting, roofing, garage doors, electrical, drywall, landscaping, irrigation, and sod. In addition, BBD is responsible for repairing any damage of the abandoned development which was left by previous builders of the property.			
<b>Role Performed</b>	<b>Contract Status</b>	<b>Performance</b>	<b>Completion Date</b>
Prime Contractor	In Process	100% Self-Performance	06/2018

<b>Project Title</b>	Wrenn Properties	Contract Amt.	\$180,000
<b>Location</b>	Marceline, MO		
<b>Description</b>			
The project included complete demolition, remodels, new builds, fencing, and concrete.			
<b>Role Performed</b>	<b>Contract Status</b>	<b>Performance</b>	<b>Completion Date</b>
Prime Contractor	In-Process	100% Self-Performed	TBD

<b>Project Title</b>	Miller Landscape	Contract Amt.	\$138,000
<b>Location</b>	Chillicothe, MO		
<b>Description</b>			
Project consisted of complete removal and replacement of a large landscape. This included the removal of most of the existing plants and edging. BBD built a retaining wall with landscape lighting.			
<b>Role Performed</b>	<b>Contract Status</b>	<b>Performance</b>	<b>Completion Date</b>
Prime Contractor	Complete	100% Self-Performance	04/2017